CAPSULE SUMMARY

Survey # F-3-154
Street Address Opossumtown Pike at Willow Brook Farm Town, State Frederick, Maryland 21701
private _x , public ____

Approximate date <u>ca. 1860</u>

The farmstead at Willow Brook Farm was originally accessed by a straight farm lane leading in an easterly direction from Opossumtown Pike at its junction with Willow Brook Farm. The farm access lane has been replaced with the network of streets constructed to serve the Willow Brook subdivision now under construction. The farmstead consists of a two story five bay brick house dating from ca. 1860 and a frame early 20th century wagon shed. A stone end bank barn, an equipment shed and a ca. 1920-30 dairy barn and milk house of rock-faced concrete block, once part of the complex have been demolished. The property is located approximately 1/4 mile east of the road with the house facing west, toward the road and the outbuilding sites immediately north of the house.

The house at Willow Brook Farm is a very intact example of a prosperous farmer's residence of the third quarter of the 19th century. Most significant about the property is its pristine interior which includes original paint finishes in several rooms, original door hardware throughout and rare examples of surviving curtain and interior blind hardware. All woodwork, doors, floors and mantlepieces remain intact as well, which is unusual in houses owned by people with the financial wherewithal to have made changes and alterations over the years. Changes and modifications for this dwelling have been limited for the most part to the north addition, and to re-bricking the two north fireplaces in the main section. First floor woodwork in the north of the main house was grain painted to resemble oak, probably about 1890-1910.

Maryland Historical Trust State Historic Sites Inventory Form

Survey No. F-3-154

Magi No.

DOE ___ yes ___ no

1 Name of	Droporty					
1. Name of		ate preferred name)				
historic Willow	Brook Farm					
and/or common						
2. Location						
street & number O	possumtown Pike a	t Willow Brook Farm	n		not for p	ublication
city, town Frede	erick	vicinity of		congressional	district	
state Maryla	and	county	Frederick			
3. Classifica	ation					
Category district) _X building(s) structure site object	Ownership public _X private both Public Acquisition in process being considered not applicable	Status occupied unoccupied work in progress Accessible yes: restricted yes: unrestricted yno	Present Use agriculti comme educatii entertaii governr industria military	rcial onal nment nent	museum park private re religious scientific transport other: V	esidence : tation
4. Owner of	Property (give	names and mailing address	ses of <u>all</u> owner	s)		
name Frede	erick Farms LC			· · · · · · · · · · · · · · · · · · ·		
street & number 2	900 Linden Lane	Suite 291	telephone	no.:		
city, town Silve	er Spring	state a	nd zip code	Maryland	20910	
5. Location	of Legal Descr	iption				
courthouse, registry of	of deeds, etc. Freder	ick County Courthou	ıse		Liber	1897
street & number We	est Patrick Stree	E			Folio	209
city, town Freder	ick		state	Maryland 2	1701	
6. Represen	tation in Existi	ng Historical Surveys				
title			-··			
date			federal	state	county	local
depository for survey	records					
city, town			state			
						

7. Description		Survey No. F-3-154
Condition excellent deteriorated good ruins fair unexposed	Check one unaltered X altered	Check one X original site moved date of move

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Summary Description

The farmstead at Willow Brook Farm was originally accessed by a straight farm lane leading in an easterly direction from Opossumtown Pike at its junction with Willow Brook Road. The farm access lane has been replaced with the network of streets constructed to serve the Willow Brook subdivision now under construction. The farmstead consists of a two story five bay brick house dating from ca. 1860 and a frame early 20th century wagon shed. A stone end bank barn, an equipment shed and a ca. 1920-30 dairy barn and milk house of rock-faced concrete block, once part of the complex have been demolished. The property is located approximately 1/4 mile east of the road with the house facing west, toward the road and the outbuilding sites immediately north of the house.

General Description

The Willow Brook farmhouse is a two story, five bay brick building resting on fieldstone foundations. The walls have a facing of all stretcher bricks and are painted white. Both the front (west) and rear (east) facades are formally arranged with five bays and a central entrance. The west-facing front is unusual for farmhouses in mid-Maryland which typically face south or southeast.

Windows have six over six light sash within narrow frames, beneath wooden lintels. Most windows retain their original sash and glass. They have pairs of louvered shutters. The fenestration pattern at the rear of the building was made formal and symmetrical like the front, although the rear entrance is treated much more simply than the front one. The main entrance has a two-leafed door, with each leaf having a long vertical panel. The door is surrounded by a transom and sidelights with diamond-shaped panes. A one-bay entrance porch supported by square columns shelters the entrance. There was also a one-bay shed-roofed rear porch, but it was removed ca. 1996.

Attached to the west end of the house is a two story, two bay shed-roofed kitchen addition which appears to date from the 1870s. The east end of the north wall of this section has a recessed double porch. Later partitions, paneling and details of the interior of this addition have been removed recently. The addition contains two large rooms per story, but its stone foundations do not match its current configuration, revealing that the foundations were for an older building now gone. The foundations included a chimney pier, although there is no fireplace in the addition. Also fragments of 18th century pottery and glass were found during excavations of the cellar. In addition, two doors at the second story level of the addition have six raised panels and predate the rest of the building. Until recently, this portion of the house held the kitchen and bathroom.

The house is roofed with standing seam sheet metal over earlier wooden shingles. There are double brick chimneys inside each end and brick parapet walls.

The interior of the main section of the house is divided formally with two rooms on either side of a broad central stair and entrance hall. The staircase is along the south wall of the hall, set well back from the front door. The newel post and balusters are turned. To the north of the hallway are the more formal rooms, separated by a large opening with a flat architrave with plain corner blocks. Mantlepieces are matched with panels with multiple receding fields. Windows have similar architraves with paneled dadoes beneath the sills. Woodwork in these rooms, the hallway and the addition has been grain painted to resemble oak, a treatment which probably was done about the turn of the 20th century.

Maryland Historical Trust State Historic Sites Inventory Form

Survey No. F-3-154

Magi No.

DOE ___ yes ___ no

Section Number ____7 Page ____2

The two rooms to the south of the hallway have matched mantlepieces with molded trim in the form of shallow Gothic arches. In the rear room at the southeast corner of the house is a narrow enclosed stair, rising parallel to the main stair. Apparently constructed at the same time as the rest of this section of the house, it seems to have been a servant's stairs leading to separate quarters on the second floor and to the cellar accessed by a flight of steps beneath the main staircase. Original mahogany grain painting remain on doors and trim in the southeast room.

The second floor is divided into five rooms, two on each side of the hallway and one at the front (west) end of the hallway. The second floor south rooms are appointed similarly to those beneath them on the first floor. They retain original paints, peg rails and hardware. The paint colors are three-tone, "drab" (a 19th century term for medium brownish-grey), putty and white. Baseboards are a darker brownish grey. A west window in the north room has two porcelain knobs in its jamb meant for wrapping the cord from curtains or roller blinds. They are original to the house and are rare survivals.

The house appears to be in good condition despite its having been vacant for some time. Other buildings on the property included a large stone bank barn, a tile silo, a rock-faced concrete block and frame dairy barn with a gambrel roof, probably dating from the 1920s or '30s, and a semi attached milk house, also of rock-faced concrete block. All of these buildings have been removed. Surviving is a frame corn crib and wagon shed. The wagon shed has open gable ends to allow for wagon access and maximum air circulation for the side corn storage bins. It is a timber framed building resting on field stone piers. The framing is mortised and tenoned with pegged joints. The framing members have circular saw marks. A combination of wooden materials side the building, including German siding and board and batten. Doors of narrow tongue and groove boards hung on a roller tracks have been added to the front and rear of the building. The corn crib/wagon shed appears to date from the early 20th century. The framing and finish materials may have been recycled from another building.

8. Signification	ance		Survey No. F-3-15	54
Period prehistoric 1400-1499 1500-1599 1600-1699 1700-1799X 1800-1899 1900-	Areas of Significance archeology-prehistoric archeology-historic agricultureX architecture art commerce communications	Check and justify below community planning landscap conservation law economics literature education military engineering music exploration/settlement philosopi industry politics/g invention	soci hur ny thea overnment tran	ence Ipture ial/ manitarian
Specific dates	Builder/Archit	ect		
and/o Applicable	Exceptions:AB _	D CDEFG rate _ <u>x</u> local		

Prepare both a summary paragraph of significance and a general statement of history and support.

SIGNIFICANCE SUMMARY:

Summary

The house at Willow Brook Farm is a very intact example of a prosperous farmer's residence of the third quarter of the 19th century. Most significant about the property is its pristine interior which includes original paint finishes in several rooms, original door hardware throughout and rare examples of surviving curtain and interior blind hardware. All woodwork, doors, floors and mantlepieces remain intact as well, which is unusual in houses owned by people with the financial wherewithal to have made changes and alterations over the years. Changes and modifications for this dwelling have been limited for the most part to the north addition, and to re-bricking the two north fireplaces in the main section. First floor woodwork in the north of the main house was grain painted to resemble oak, probably about 1890-1910.

Historic Context

Frederick County and central Maryland in general were settled during the second half of the 18th century although there were habitations in the region as early as the 1720s. Although land was initially held by English entrepreneurs from eastern Maryland, the majority of settlers who actually lived in Frederick County were Germans who had migrated south from Pennsylvania. The area developed into a prime agricultural region with emphasis on the production of small grains. With grain farming dominating, related industries and transportation networks soon developed. Grist and flour milling was prevalent, as was distilling. Central Maryland along with south central Pennsylvania grew in importance as an agricultural region. In Maryland, Frederick and adjoining Washington County led the state in wheat and corn production throughout most of the 19th century. During the Civil War the allure of the agricultural prosperity of central Maryland influenced Robert E. Lee's plan to invade Maryland in the late summer of 1862. The greater region was the nation's bread basket until large scale grain production in the Midwest overtook local production in the later 19th century.

Resource History

On both the Frederick County Atlas of 1873 and the 1858 Isaac Bond map, this property is shown as belonging to D. Glaze. The house is apparently located just west of the site of Franklin Mills which were on the east side of Tuscarora Creek. The mill and its surrounding farm was the homestead of the Cronise family. Joseph Cronise eventually owned this farm as well The appearance of the house suggests that it was built during

Maryland Historical Trust State Historic Sites Inventory Form

Survey No. F-3-154

Magi No.

Section Number 8 Page 2

the third quarter of the 19th century, probably in the 1860s.

Willow Brook Farm's history seems consistent with the physical evaluation of the house. The property was purchased by David Glaze on February 18, 1853. He purchased approximately 237 acres from William Ross for \$16,030.16. The relatively high price suggests that improvements were already present. The excavated foundations beneath the west half of the addition affirm that an earlier building preceded the present house.

William Ross was a trustee appointed to sell the property for Sophia Fitzhugh who had received the farm from Benjamin Fitzhugh and his wife (presumably Sophia's parents), on January 16, 1849. Benjamin Fitzhugh purchased the property from Henry Schley on June 2, 1848. It was part of the land grant "Taskers Chance."

David Glaze and his wife Elizabeth owned the property until his death, when it was old by his heirs to Joseph Cronise, on March 6, 1873 for \$21,611.08. At this time the farm contained the same acreage, 237. The property remained in the Cronise family until an equity court proceeding among various members of the family resulted in sale of the property on November 10, 1924 for \$15,587.10. By this transaction, however, the acreage was reduced to 124 acres and 32 perches. The purchaser in 1924 was C. Raymond Crum. The property remained in the Crum family until the present subdivision which began in 1993.

The present house was most likely built by David Glaze during the 20 year period of his ownership between 1853 and 1873. (Deed references: Liber 1897, folio 209, May 3, 1993., Liber 1095, folio 187, Aug. 31, 1979; Liber 358, folio 255, May 22, 1926; Liber 358, folio 254, May 22, 1926; Liber 350, folio 385, November 19, 1924; Liber CM9, folio 534, March 6, 1873; Liber ESI, folio 615, February 18, 1853; Liber WBT, folio 608, January 6, 1849; Liber WBT7, folio 258, June 2, 1848.

Resource Analysis

The principal significance of this house is its intact architectural quality. It has rare surviving details, such as window and curtain hardware, latches, knobs and window glass. Although the farm house has been detached from its setting and other buildings from its grouping have been eliminated, it appears to be eligible for listing in the National Register of Historic Places under Criterion C for its architecture. The attributed construction date from the third quarter of the 19th century is based on several features from that period which include the all stretcher bond facade, the diamond pane transom and sidelights, the double-leafed front door with single vertical panels, the interior doors with two vertical panels and the mantlepieces with Gothic pointed arch friezes. These features are all characteristic of the third quarter of the 19th century in central Maryland, and are most typical of the 1860s.

Maryland Historical Trust State Historic Sites Inventory Form

Survey No. F-3-154

Magi No.

DOE ___ yes ___ no

Section Number ____8 Page ___3

HISTORICAL CONTEXT:

MARYLAND COMPREHENSIVE PRESERVATION PLAN DATA

Geographic Organization: Western Maryland

Chronological/Developmental Period(s):

Agricultural-Industrial Transition 1815-1870 A.D.

Prehistoric/Historic Period Theme(s):

Architectural/Landscape Architecture/Community Planning

Resource Type:

Category: Farmstead

Historic Environment: Rural

Historic Function(s) and Use(s):

Domestic/single dwelling

Known Design Source: Vernacular, Greek Revival Influence

9. Major Bibliographical References

Bond, Isaac, Map of Frederick County, Maryland. E. Sachse and Co., Baltimore, 1858.

Ballweber, Hettie L., "Phase 1 Archeological Survey Willowbrook Subdivision, Frederick County, Maryland," ACS Consultants, Columbia MD, July, 1995.

Survey No. F-3-154

Lake, D. J., Atlas of Frederick County, Maryland, C.O. Titus and Co., Philadelphia, PA, 1873.

Scharf, J. Thomas, History of Western Maryland, 1882. Baltimore: Regional Publishing Co., 1968. (reprinted).

Williams, T.J.C. and Folger McKinsey, History of Frederick County, Maryland, 1967.

10. Geographical Data

Acreage of nominated property 17,600 square feet	
Quadrangle name <u>Frederick</u>	Quadrangle scale 1:24,000
UTM References DO NOT COMPLETE UTM REFERENCES	
A Zone Easting Northing Zone Easting Northing	B
C	D —
E	
$G \stackrel{ }{\longleftarrow} I \stackrel{ }{\longrightarrow} I \stackrel{ }{\longleftarrow} I \stackrel{ }{\longleftarrow} I \stackrel{ }{\longleftarrow} I \stackrel{ }{\longleftarrow} I \stackrel{ }{\longrightarrow} I \stackrel{ }{\longleftarrow} I \stackrel{ }{\longrightarrow} I $	H ————

Verbal boundary description and justification

VERBAL BOUNDARY DESCRIPTION:

The boundary of the house remaining on at Willow Brook Farm is shown as lot #36 on the preliminary pla of the Willow Brook Farm Subdivision. The lot measures 11' x 120' x 215'. The house is approximately centered in the lot.

BOUNDARY JUSTIFICATION:

This lot is the entire property to be associated with this house as it becomes part of the Willowbrook Subdivision.

List all states and counties for properties overlapping state or county boundaries				
state	code	county	code	
state	code	county	code	

11. Form Prepared By


name/title Paul	a S. Reed, PhD, Architectural Hi	storian
organization Pau	la S. Reed and Associates, Inc.	date July, 1997
street & number	105 N. Potomac Street	telephone 301-739-2070
city or town	Hagerstown	state Maryland


The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust People's Resource Center 100 Community Place Crownsville, MD 21032-2023 410-514-7000







F-3-154 Willow brook Farm house Frederick Co., MD photo by P Reed neg loc. Paula S Reed + Assoc Inc. Hagerstown, MD Front west elevation = view # 1 07 23



F-3-154 Willawbrook Formhouse Frederick Co., MD Photo by P. Reed 6/97 reg, cor. Paula & Reed + Assoc Inc Hagerstown MD 21740 North elevation, SE views

#2 0423



F-3-154 Willowbrook Farmhouse Frederick Co., MD photo by P. Reed 6/97 neg. Lor, Paula S. Reed + Assoc. Inc. Hagerstown MD 21740 E. elevation W View

#3 0423



F-3-154 Willowbrook Farmhouse Frederick Co, MD photo by P Leed 6/97 neg, loc. Paule S. Reed & Assoc, Inc. Hagerstown, MD 21740 SWULL, NIE Elevations

4 07 23



F-3-154 Willowbrook Farmhause Frederick Co, MD photo by P Reed 6/97 rig. Loc. Pauls S Reed + Assoc. Inc. Hagerstown, MD 21740 Entrance and Star hall

5 9 23



F-3-154 Willowbruk Frankonse Frederick County MI) photo by P. Reed 6197 rig. loc. Hanla S. Reel + Assoc. Inc. Hagerstown, MD Z1740 Interior routhwest room, first floor looking into no Theast room # 6 9 23



F-3-154 Willowbrook Farmhouse Frederick Co, MD photo by P. Reed nig. W. Paula S Reed + Assoc Inc. Hagerstown, MD 21740 first floor, Sw room, grain painted doors (organd) #19-23



F-3-154 Willowbrook Firmhouse Frederick Co, MD photo by P. Reed 6/97 neg, Loc. Paula S. Reel + Assoc Inc Hagerstown, MD 21740 back stars (Servants) #8 4 23



F-3-154 Willowbrox Farmhouse Frederick Co., MD Photo by P. Reed 6/97 neg. Loc. Paula S Reed + Assoc Inc. Hag istown, ND Second floor, northerest room with view into northeest room #9423



F-3-154 Willowbrook Farmhouse Fredrick Con MD Photo by P. Reed 6/4reg, Low Paula S. Reed + Assoc Inc. Hageistown MD

Second floor, Normwest room, with ariginal blind cord wrap hardware

10 4.23



F-3-154 Willow brook Farming == Frederick Co NIS Photo by P. Reed 6197 neg loc. Paulo 5 Red , Assoc Inc Hagerstown MD 21740 Second floor, Southeast with Uses into Southwest som #11 04 23



F-3-154 Willaubiak Farmhouse Frederick County, MD photo by P. Reed nig ler Paula S. Reed + Assor, Inc. Hagerstown, MD 21140 Interior east room, first story addition, bolling into west room #12 9 23



F-3-154 Willowbrook Farm house Frederick Co, MD photo by Pikel neg be. Paula S. Reel + Assoc Inc Hagerstown, MD 21740 Cellar foundation beneath addition, possibly 181 Century #13 0 23



F-3-154 Willowbrook Farmhouse Frederick Co., MD photo by P. Reed 6/97 neg, low. Paula S. Reed and Assex. Inc. Hagerstown, Mi) Second floor, with addition #14 07 23



F-3-154 Willowbrook Firmhouse Frederick Co, MD Photo by P. Reed neg be. Paula S. Reed + ASSOC, Inc Hagerstown, MD Sevond floor, addition #15 of 23



F-3-154 Willaubrook Farmhouse Frederick Co. MD photo by P. Reed neg, Loc. Paula S. Leed + ASSOC, Inc. Hagerstown, MD Attic, roof structure #16 04-23



F-3-154 Willowbrook Farmhouse Frederick Co, MD photo by P. Reed neg, loc. Paula S. Reed + Assoc, Inc. Hagerstown, MD Com crib and site of farm buildings, N. vous # 17 of 23



F-3-154 Willowbrook Farmhouse Frederick Co, MD Photo by P. Reed neg, loc. Paula S. Reed + Assoc Inc Hagerstown, MD Corn arib, NE view, and Site of farmbuildings #18 423



F-3-154 Willowbrook Farmhouse Frederick Co, MD photo by P. Reed 6/97 neg. loc. Paula S. Reel + Assor, Inc. Hagerstown, MD 21740 Com conb/ wagon stred, New view, S+E elevations #19 % 23




F-3-154 Willawbrook Farmhouse Frederick Co, MD proto by P. Reed neg. low Haula S. Reed + Assoc, Inc. Hagerstown, MD 21740 Com CVID, NIE Elevations, Sw vent # 20 4 23



F-3-154 Willowbrook Farmhouse Frederick Co, MD photo by P. Reed reg. Low Paula S. Reed + Assoc Inc Hagerstown, MD 21740 Interior, wagon sheel #21 \$ 23



F-3-154 Willowbook Farmhouse Frederick Co, MD photo by & Reed 6/97 neg, loc, taule S Reed + Assoc, Inc. Hagerstown, MD 21740. Interior, wagon shed # 22 0 23



F-3-15A Willowbrook Farmhouse Frederick Co, MD photo by P. Reel 6/97 neg loc. Paula S. Reed , Assoc Inc Hagerstown, MD 31740 Interior, coin crb # 23 9 23